JCE Infrastructure Pty Ltd

ABN 29 699 165 663 | Phone 0477 207 027 | jayden@jceinfrastructure.com.au
756 Quia Road, Gunnedah NSW 2380 | Civil and hydraulic engineering

REQUEST FOR QUOTATION

Mechanical and Electrical Verification, PS C6B (Contract 2)

Vickers Road PS C6B Diversion Project: Superintendent and Construction Verification Services

Date	12/10/2026	**RFQ no.**	JCE-RFQ-VP528755-ME (Final)
Quote due	12:00 pm AEST Friday 23/10/2026	**Head tender closes**	5:00 pm AEST Friday 30/10/2026
Client	Townsville City Council (QLD)	**Council reference**	TCW00728 (VendorPanel VP528755)
From	Jayden Callen, Director	**Contact**	0477 207 027, jayden@jceinfrastructure.com.au

To: Clarence Consultants (attention Ken Heard)

1. Background

Townsville City Council (Council) has invited quotations under RFQ TCW00728 for an independent Superintendent and construction verification services for the Vickers Road PS C6B Diversion Project. Flow from PS C6B (North Vickers Rd, Condon) will be diverted from Condon STP to Mount St John STP. AECOM is the designer. The works will be built under three Construct Only lump sum contracts on Council's modified AS 4000-1997:

Contract	Works	Construction period
Contract 1	Element 3: Stage 1 pressure main, DN560 PE, about 4,290 m along Kern Main Drain to Dalrymple Rd, with crossings of the Townsville Ring Road and Hervey Range Road in existing envelopers	December 2026 to January 2028 (61 weeks)
Contract 2	Elements 1 and 2: PS C6B structural, pipework, access road, electrical and control upgrade, and a new odour control unit designed and constructed by the Contractor to AECOM's performance specification	July 2027 to November 2028 (74 weeks)
Contract 3	Element 4: Stage 2 pressure main, DN710 PE about 7,600 m (Dalrymple Rd to Everett St, crossings of Dalrymple Rd, Woolcock St and the North Coast Railway in envelopers), then DN900 PE about 3,320 m to the Mt St John STP inlet works	March 2028 to July 2029 (74 weeks)

Each construction contract has a 12-month defects liability period. The consultancy starts on 11/12/2026 (anticipated award) and its date for completion is 30/06/2030. Council will pay for hours worked at the quoted rates, up to a not-to-exceed allowance per task, under its amended AS 4122-2010 consultancy contract. Council scores the nominated individuals' capability (50%), methodology (35%), local industry participation (10%) and social benefit and Indigenous engagement (5%).

JCE Infrastructure Pty Ltd (JCE) will quote to Council as the Superintendent and asks for your quotation as a declared subconsultant. Section E clause 19 of Council's RFQ requires subconsultants to be declared at tender, and clause 20 of the contract requires Council's approval to subcontract.

2. Roles and site presence

Role	Provided by	Site presence
Superintendent	JCE (Jayden Callen). Signs every notice, direction, certificate and determination, and releases hold points.	Key hold points, shutdowns and PC inspection in person.

Role	Provided by	Site presence
Superintendent's Representative and Inspectors	A Townsville partner engaged by JCE.	Daily inspections while work is under way.
M&E verification (Contract 2 only)	Your firm. Reviews and witnesses the mechanical, electrical, controls and odour control work and recommends hold point releases to the Superintendent.	Called off by JCE to match the Contractor's submittals and test dates: about 8 to 12 attendances at PS C6B (North Vickers Rd, Condon) between July 2027 and November 2028, plus factory tests if Council requires them. Document review can be done remotely.

3. Scope of services

- **Submittal review:** review the Contractor's mechanical, electrical and controls submittals for PS C6B (pumps, valves and pipework, switchboard and MCC drawings, SCADA and telemetry functional description, odour control unit design to AECOM's performance specification) against the contract specification and TCC standard specifications, and give written comments to the Superintendent.
- **Factory acceptance tests:** witness switchboard and pump FATs where Council requires them.
- **Installation inspections:** inspect the mechanical and electrical installation at the hold and witness points in the Contractor's ITPs.
- **Site acceptance and commissioning:** witness site acceptance tests and SCADA and telemetry commissioning with Council's operations staff.
- **Odour control unit:** witness performance testing against AECOM's performance specification, and review commissioning records and O&M manuals before Practical Completion.
- **Reporting:** a short report for each attendance, recommended hold point releases, and input to the PC defects list and the Contract 2 Completion Report.

4. Indicative hours and program

About 150 hours across Contract 2 (July 2027 to November 2028), within Council's Inspector allowance. JCE will call off attendances as needed; hours are not guaranteed.

Activity	Indicative hours
Submittal review (mechanical, electrical, SCADA, odour control unit)	40
Factory acceptance test witnessing (if Council requires FAT)	30
Installation inspections at hold and witness points	30
Site acceptance tests and SCADA and telemetry commissioning	30
Odour control unit performance testing and O&M review	20
Total	**150**

5. Deliverables

Deliverable	Format	Timing
Submittal review comments	Excel or PDF register	Within 5 working days of receipt
Inspection and test attendance reports with recommended hold point releases	PDF	Within 2 working days of the attendance
Input to the PC defects list and Contract 2 Completion Report	Word or Excel	At PC and at finalisation

6. Qualifications and RPEQ

- The services are carried out in Queensland. Under the Professional Engineers Act 2002 (Qld), professional engineering services must be carried out by an RPEQ or under the direct supervision of an RPEQ. Council's RFQ does not name a registration, but JCE's Superintendent is not an RPEQ.
- The engineer who signs submittal reviews and test reports must be an RPEQ in the electrical or mechanical area, or work under the direct supervision of a named RPEQ in your firm. Please give registration numbers.
- Experience wanted: sewage pump station mechanical and electrical works, switchboards and MCCs, SCADA and telemetry, and odour control commissioning for local government or water authorities.

7. Insurances

Please hold, and confirm in your quotation, insurances matching Council's contract:

- **Public liability:** $20 million for any one occurrence (contract Annexure item 30.2), with Council noted as an interested party.
- **Professional indemnity:** $10 million for any one claim with at least one automatic reinstatement (contract Annexure item 30.4). If your cover is lower, state the amount; JCE will confirm whether it is acceptable.
- **Workers compensation:** a current WorkCover Queensland policy for all workers you engage on this project. Council's Stage 1 threshold asks for a WorkCover Queensland certificate.
- Certificates of currency for each policy, with expiry dates, attached to your quotation, and the policies kept current to 30/06/2030.

8. Work health and safety and systems

- Your own WHS management system and site-specific SWMS.
- Registration and validation in Council's Contractor Management System and completion of the TCC online safety induction before starting, plus each construction Contractor's site induction.
- Compliance with each Contractor's site rules. Neither JCE nor your firm is the Principal Contractor.

9. Independence and conflict of interest

- Declare any current or past relationship (employment, contract, joint venture or financial interest) with AECOM, with Council staff on this project, or with any party likely to tender for Contracts 1 to 3.
- If engaged, you must stay independent of the construction contractors and their subcontractors for the life of the engagement, and must not tender for or carry out work for them on this project.
- Notify JCE in writing straight away if a conflict arises later. JCE will declare your position in Council's Schedule of Conflict of Interest.

10. Confidentiality

- This request and Council's documents are confidential. Use them only to prepare your quotation and do not pass them to any other party.
- Do not contact Council about TCW00728. Council directs all enquiries through VendorPanel. Send your questions to JCE and JCE will raise them with Council if needed (Council's question cut-off is 5:00 pm AEST Friday 23/10/2026).
- JCE will keep your prices confidential and will use your company profile, CVs and certificates only in its quotation to Council. Council has advised that quotations may be disclosed under the Right to Information Act 2009 (Qld) and the Local Government Regulation 2012 (Qld).

11. Information provided

Sent with this request: Council's Request for Quotation (TCW00728), the amended AS 4122-2010 consultancy contract and Council's Price Schedule V3. Council has not yet issued Appendix E.1 (design drawings), Appendix E.2 (AS 4000 administration table) or the construction contracts. JCE will ask Council for them and will pass on any addenda.

12. What to include in your quotation

- Completed pricing schedule (section 13), exclusions and validity.
- CVs (2 pages each) for the proposed engineer or engineers and a backup, with RPEQ numbers and two referees each.
- Company profile, office address and post code, and any work for Townsville City Council in the last 3 years.
- Similar projects in the last 5 years (client, contact, scope, value, period).
- Certificates of currency (public liability, professional indemnity, WorkCover Queensland or, for staff based outside Queensland, the relevant workers compensation policy).
- Conflict of interest declaration (section 9) and confirmation of WHS system and SWMS.

13. Pricing schedule

Prices in AUD, excluding GST. Rates must be all-inclusive (vehicle, fuel, phone, laptop and software, PPE, tools, and travel within Townsville). Council pays no separate disbursements, so price any travel from outside Townsville in item B6 or B7.

Item	Description	Hours	Rate (ex GST)	Amount (ex GST)
A1	Hourly rate, senior electrical or controls engineer (RPEQ)		$_____ /h	
A2	Hourly rate, mechanical engineer (RPEQ)		$_____ /h	
A3	Hourly rate, backup engineer (if different)		$_____ /h	
B1	Submittal review (lump sum, not to exceed)	40		$_____
B2	FAT witnessing, if required (lump sum, excluding travel)	30		$_____
B3	Installation inspections (lump sum, not to exceed)	30		$_____
B4	SAT and SCADA and telemetry commissioning (lump sum, not to exceed)	30		$_____
B5	Odour control unit performance testing and O&M review (lump sum, not to exceed)	20		$_____
B6	Travel and expenses for each FAT day outside Townsville, if required		$_____ /day	$_____
B7	Travel to PS C6B from your base, if outside Townsville (per attendance)		$_____ /trip	$_____
	Total, items B1 to B5 (excluding GST)	**150**		**$_____**

- **Exclusions:** list every exclusion and assumption. Anything not listed is taken as included.
- **Validity:** prices to remain valid for at least 90 days from 23/10/2026 (to 21/01/2027). Council's quotation validity is 150 days from 30/10/2026; please say whether you will extend if Council's award is later than 21/01/2027.
- **Rates over time:** the work falls between July 2027 and November 2028. State whether rates hold for that period or give the escalation basis.
- **Hours:** state any minimum call-out or minimum daily charge.

14. Conditions

- Any engagement depends on JCE being awarded the contract by Council and on Council approving your firm and your nominated people. JCE does not pay for the preparation of quotations.
- The subcontract will be on terms back to back with Council's amended AS 4122-2010, including payment within 30 business days after a valid payment claim (Annexure item 8), monthly claims, and Council's limit of liability.
- Hours are Council's estimates and are not guaranteed. Construction contract dates are Council's indicative program and may move. Additional hours caused by later award or longer construction periods will be paid at your quoted rates if Council pays JCE for them.

- Nominated personnel may be changed only with JCE's and Council's approval (contract clause 18.1), with a CV showing equivalent experience.

15. Submission

Please email your quotation, CVs and certificates to jayden@jceinfrastructure.com.au by **12:00 pm AEST Friday 23/10/2026**. JCE needs that week to name your people in Council's schedules before the head tender closes at 5:00 pm AEST Friday 30/10/2026. Questions to Jayden Callen on 0477 207 027.

Yours faithfully,

Jayden Callen
Director, JCE Infrastructure Pty Ltd
0477 207 027 | jayden@jceinfrastructure.com.au