JCE Infrastructure Pty Ltd
ABN 29 699 165 663 | 0477 207 027 | jayden@jceinfrastructure.com.au
756 Quia Road, Gunnedah NSW 2380 | Civil and hydraulic engineering

REQUEST FOR QUOTATION

Road, roadside and ancillary asset imaging and condition data

Murray River Council tender MRC-2645, Infrastructure Asset Condition Assessments (VendorPanel VP527277)

To	[Firm] (invited firm, as named in the covering email)
From	Jayden Callen, Director, JCE Infrastructure Pty Ltd
Date	12/10/2026
RFQ number	JCE-RFQ-VP527277-01 (Rev B, final)
Quote due	**12:00 pm, Wednesday 28/10/2026**
Tender closes	2:00 pm, Friday 13/11/2026 (Council's VendorPanel close)
Confirm you will quote	By Monday 19/10/2026
Questions to JCE	By 12:00 pm, Wednesday 21/10/2026
Status	Pricing request for a tender. Any engagement depends on JCE winning the contract.

Dear Sir or Madam,

JCE invites you to quote for the geo-referenced imaging, inventory and condition rating of Murray River Council's road network and its roadside and ancillary assets, as JCE's imaging partner and key subconsultant in its tender for MRC-2645.

1.0 Project and tender background

Murray River Council (Council) has invited tenders (MRC-2645, VendorPanel VP527277) for the inspection, condition assessment, remaining useful life and comprehensive valuation of all transport and bridge infrastructure across the Murray River LGA, in four zones: Barham, Mathoura, Moama and Moulamein. The first valuation is as at 30/06/2027. A rolling program follows, with one zone physically inspected each year from 2028 to 2031 and a valuation by 30 June each year.

Council wants one supplier and one lump sum, broken down by asset category and valuation year. JCE Infrastructure (JCE) is tendering as Lead Consultant. JCE is responsible for the methodology, quality control, data, remaining life, defect and safety assessment, 10-year programs, the valuation and reporting, and works with specialist partners for road imaging, bridge inspection and valuation sign-off.

Council's Appendix 1 quantities for your scope (to be verified by inspection):

Asset class	Quantity	Condition rating	Images
Sealed roads: urban; regional; local	1,110 km (133; 416; 561)	Per segment and component (surface, pavement, formation)	Every 10 m
Unsealed roads	1,890 km	Per segment (wearing course, formation)	Every 10 m
Kerb and gutter	176 km	Per segment	Every 10 m
Footpaths and cycleways	121 km	Per segment	Every 10 m
Roundabouts; traffic islands; medians	21; 199; 29	Per asset	Per asset
Carparks	63	Per asset and component	Per component
Rural culverts	About 1,555 (to be confirmed)	Per asset	Per asset
Guardrail	About 500 items (to be confirmed)	Per asset, with safety data	Per asset
Bus shelters	About 35 (to be confirmed)	Per asset	Per asset
Zones (road length)	Barham 809 km; Mathoura 864 km; Moama 474 km; Moulamein 842 km	Includes a 500 m buffer past LGA and zone boundaries	

2.0 Scope of services requested

Inspection and condition rating (Year 1, all four zones)

- Condition rating on Council's scale (1 Excellent, 2 Good, 3 Fair, 4 Poor, 5 Very Poor) for every segment and component, with defects coded to Council's defect schema. JCE supplies the rating guide, confirmed after the pilot.
- Segments: urban roads block to block (the main road owns the intersection); rural roads in 2 km segments from zero chainage. Rural roads that start in town use the rural method. Barham Road, Wakool Road and Moulamein Road are each collected whole in one zone.
- Minimum record per asset: Asset ID, name, location, component, material, dimensions, inspection date, inspector, photographs, defects with at least two images (segment overview and close-up), rating and recommended action.
- Guardrail and handrail: inventory, condition and the data JCE needs for its safety assessment against Austroads Guide to Road Design Part 6, with unprotected edge drops recorded as defects.
- All assets are recorded regardless of value, including those below Council's capitalisation thresholds.

Imaging, GPS and spatial requirements

- High-resolution, low-distortion stills that can be used to rate pavement defects, every 10 m on linear assets and of each component on complex assets, with GPS embedded natively in each image (DRFA compliant).
- Camera coverage from kerb to kerb or table drain to table drain, capturing roadside features and hazards on both sides, with offset GPS pick-up of on-road and roadside features. Please state whether you capture one lane or both lanes in one pass, including on single-lane unsealed roads.
- Image names in Council's format: Asset ID, then component or chainage, then lane direction or facing, separated by hyphens. Coordinates in GDA94 and GDA2020 (MGA zones 54 and 55), heights to AHD.
- A three-day pilot in Moama with JCE and Council before full capture; same-day notice to JCE of condition 5 and safety defects; weekly progress data.

Rolling years 2028 to 2031

- Physical inspection of one zone a year to the same specification (Barham 2028, Mathoura 2029, Moama 2030, Moulamein 2031), plus the newly acquired assets Council lists each year, with capture between February and April and data by 30 April.

3.0 Deliverables and formats

- Data in Council's Excel data template (tabs Roads, Kerb, Footpath, Culverts, Guardrail, Bus Shelter, Carparks, Roundabouts), linked to Council Asset IDs.
- Images (.jpg) with GPS metadata and an image index file; GIS layers of segments and point assets with Asset IDs and metadata.
- Defect list with ratings, images and locations, and same-day notices of condition 5 and safety defects.
- QA records: rater calibration, re-rates and completeness checks.

4.0 Program

The Year 1 field work runs from December 2026 to April 2027 so that JCE can complete the data, defect reports and valuation as at 30/06/2027. Dates assume award on Council's expected decision date of 11/12/2026.

Milestone	Date
Quote due	12:00 pm, Wednesday 28/10/2026
Tender closes	2:00 pm, Friday 13/11/2026
Award (Council's expected decision date)	Friday 11/12/2026
Your SWMS, safety plan and methodology input to JCE	Monday 14/12/2026
Hold point submissions to Council	Friday 18/12/2026
Inception and Council WHS induction, Moama	Tuesday 12/01/2027
Pilot, Moama (with JCE and Council)	27/01/2027 to 29/01/2027
Approval to proceed	Friday 05/02/2027
Network capture, all four zones	08/02/2027 to 16/04/2027
Final data, images and QA records to JCE	Friday 30/04/2027
Rolling zones 2028 to 2031	Capture February to April; data by 30 April each year

Please confirm you can meet these dates and state the staff, crews and vehicles you will commit in each period.

5.0 Information provided

- Council's Project Brief (MRC-2645_Project_Brief.pdf).
- Council's asset data template (MRC-2645_asset_data_schema-data_template_August_2026.xlsx).
- Council's Conditions of Tender and draft Consultancy Services Agreement, from JCE on request.

6.0 Insurance, WHS and quality requirements

Insurance. Item 18 of Council's draft Consultancy Services Agreement sets these minimums, which JCE will pass down to its subconsultants:

- Professional indemnity insurance of at least $5 million for each subconsultant (Item 18(c)), kept in force until seven years after Completion of the services (clause 14.1).
- Public liability insurance of at least $20 million for any one occurrence (Item 18(a)). The Agreement requires the public liability policy to cover all subconsultants unless Council approves otherwise, so please state your own cover.
- Workers compensation insurance as required by law (clause 14.1).
- Comprehensive motor vehicle insurance for project vehicles (JCE requirement).

Please state your insurer, levels of cover and expiry dates, and attach current certificates of currency.

Work health and safety. A documented WHS system; SWMS and a site-specific safety plan, which are Council hold points before any site work; Council WHS induction before site access; AS 4602 high-visibility clothing and AS 2210 footwear. No road or bridge closures without Council agreement. Council may audit site work without notice.

Quality and ISO 9001. Item 12 of the Agreement names ISO 9001 as the quality system. Please state your ISO 9001 status: whether you hold third-party ISO 9001 certification (certifier, certificate number and expiry), or, if not, the documented quality system you use. Please also describe your QA checks for this work.

Payment. Council pays the Lead Consultant against milestones each year: mobilisation 20%, inspections complete 30%, draft data 25%, draft report 15%, final data and report 10%. JCE will pay you on the same milestones.

7.0 Relevant experience and referees

Council scores Resources and Relevant Experience at 20% of the evaluation and asks for at least three similar projects with referees (Schedule 5). JCE has asked Council to confirm that partner staff, projects and referees are assessed. Your experience will carry much of this score, so please provide:

- Two or three comparable regional council network condition surveys in the last five years, preferably in NSW or northern Victoria, covering sealed and unsealed roads and roadside assets.
- Names and CVs of the project manager, raters and data lead, and the vehicles and imaging system you will use.
- For each project: client, location, scope and quantities, year, contract value, your role, and a referee (name, position, phone and email) who has agreed to be contacted.
- Your permission for JCE to name your firm and key staff in its tender and to include the projects and referees you provide.
- Local content (5% of the evaluation): any staff, office, depot, suppliers or accommodation spend in the Murray River LGA or the nearby cross-border towns, for example Echuca or Swan Hill.

8.0 Pricing schedule

Please price in Australian dollars, excluding GST. Each lump sum includes all labour, plant, travel, accommodation, processing and expenses. The 2028 to 2031 prices are lump sums for each year and include your escalation and an allowance for nominal network growth, as Council requires. JCE adds its own margin, so please do not include one for JCE.

A. Lump sums by item and asset class

Item	Description	Unit	Qty	Rate ($)	Amount ($)
R1	Mobilisation, pilot, rating guide set-up, processing, QA and outputs in Council's template (Year 1)	lump	1		
R2	Sealed roads: imaging and condition rating	km	1,110		
R3	Unsealed roads: imaging and condition rating	km	1,890		
R4	Kerb and gutter	km	176		
R5	Footpaths and cycleways	km	121		
R6	Roundabouts, traffic islands and medians	each	249		
R7	Carparks	each	63		
R8	Rural culverts	each	1,555		
R9	Guardrail: inventory, condition and safety data	each	500		
R10	Bus shelters	each	35		
	Total lump sum, Year 1 (2027), R1 to R10				
Y2	2028: Zone 1 Barham physical inspection, all classes in this RFQ (about 809 km of road, 32 km kerb, 12 km footpath), plus new assets Council lists	lump	1		
Y3	2029: Zone 2 Mathoura (about 864 km of road, 6 km kerb, 13 km footpath), plus new assets	lump	1		
Y4	2030: Zone 3 Moama (about 474 km of road, 123 km kerb, 85 km footpath), plus new assets	lump	1		
Y5	2031: Zone 4 Moulamein (about 842 km of road, 14 km kerb, 13 km footpath), plus new assets	lump	1		

B. Unit rates for added or removed quantities

Item	Description	Unit	Rate ($)
U1	Sealed road, added or removed	per km	
U2	Unsealed road, added or removed	per km	
U3	Kerb and gutter or footpath, added or removed	per km	
U4	Point asset (culvert, guardrail item, bus shelter, island, carpark), added or removed	each	
U5	Newly acquired assets in rolling years, if not in Y2 to Y5	each	

C. Hourly and day rates for directed additional work

Role or resource	Hourly rate ($)	Day rate ($)
Project manager		
Rater or inspector		
Data or GIS analyst		
Imaging crew (vehicle, driver and rater)		

Exclusions and assumptions. Please list them. Council treats qualifications in a tender as non-conforming, so keep them few and plain.

Validity. Please hold your prices for 90 days from the quote due date, that is to 26/01/2027. Council requires JCE's tender to stay open for 60 days after the 13/11/2026 close.

9.0 Confidentiality

This request, Council's documents and any JCE pricing are confidential and are provided only for preparing your quotation. Please do not share them or use them for any other purpose, and delete them if you do not quote or if JCE is unsuccessful. If JCE is successful, clause 6.4 of the Agreement binds subconsultants to keep Council's information confidential, and Council data must not be kept after completion without Council's written consent. JCE will keep your pricing confidential and use it only for this tender.

10.0 Independence and conflict of interest

Council requires tenderers to declare any actual or potential conflict of interest (Conditions of Tender clause 4.1 and Schedule 9). Please tell us in your quotation:

- whether you are tendering for MRC-2645 yourself or quoting to other tenderers (this does not rule you out, but JCE needs to know, and JCE's documents must not be shared with them);
- any current or past work for Murray River Council on these assets, including the previous inspection and valuation cycle; and
- any relationship with Council staff or Councillors that should be declared.

11.0 Basis of engagement

- Your engagement depends on Council awarding the contract to JCE and approving you as a subconsultant (clause 8 of the Agreement requires Council's prior written approval). This request is not an engagement, and JCE does not pay for preparing quotations.
- If JCE is successful, JCE will engage you on a subconsultancy agreement that passes down the relevant terms of Council's Agreement, including insurance, WHS, confidentiality, records and payment on Council's milestones. Council expects to decide by 11/12/2026.

12.0 How to respond

Please email your quotation to jayden@jceinfrastructure.com.au by 12:00 pm, Wednesday 28/10/2026, with:

- the completed pricing schedule (parts A to C), exclusions and assumptions;
- a short methodology for your scope, including equipment and access;
- company profile, key staff CVs, three similar projects with referees, and your conflict of interest statement;
- certificates of currency for the insurances in section 6.0.

Please confirm by Monday 19/10/2026 whether you will quote. Questions are welcome by phone on 0477 207 027 or by email. Questions received by 12:00 pm, Wednesday 21/10/2026 can still be put to Council if needed.

Yours faithfully,

Jayden Callen
Director
JCE Infrastructure Pty Ltd | ABN 29 699 165 663
0477 207 027 | jayden@jceinfrastructure.com.au